

Project Verification Report

2021

COVER PAGE	
Project Verification Report Form (VR)	
BASIC INFORMATION	
Name of approved UCR Project Verifier / Reference No.	Enviance Services Private Limited
Type of Accreditation	☐ CDM or other GHG Accreditation ☒ ISO 14065 Accreditation
Approved UCR Scopes and GHG Sectoral scopes for Project Verification	01 Energy industries (Renewable/Non-Renewable Sources)
Validity of UCR approval of Verifier	30/09/2027
Completion date of this VR	09/04/2025
Title of the project activity	136.5 MW Wind Power Projects in Brazil by Babilônia
Project reference no. (as provided by UCR Program)	387
Name of Entity requesting verification service (can be Project Owners themselves or any Entity having authorization of Project Owners, example aggregator.)	UCR ID – 387 Kosher Climate India Private Limited Name: Narendra Kumar Email ID – narendra@kosherclimate.com
Contact details of the representative of the Entity, requesting verification service (Focal Point assigned for all communications)	UCR ID – 387 Kosher Climate India Private Limited Name: Narendra Kumar Email ID – narendra@kosherclimate.com
Country where project is located	Brazil

Applied methodologies (approved methodologies by UCR Standard used)	ACM0002., Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 21.0
GHG Sectoral scopes linked to the applied methodologies	01 Energy industries (Renewable/Non-Renewable Sources)
Project Verification Criteria: Mandatory requirements to be assessed	☒ UCR Standard ☒ Applicable Approved Methodology ☒ Applicable Legal requirements /rules of host country ☒ Eligibility of the Project Type ☒ Start date of the Project activity ☒ Meet applicability conditions in the applied methodology ☒ Credible Baseline ☒ Do No Harm Test ☒ Emission Reduction calculations ☒ Monitoring Report ☒ No GHG Double Counting ☐ Others (please mention below)
Project Verification Criteria: Optional requirements to be assessed	☒ Environmental Safeguards Standard and do-no-harm criteria ☒ Social Safeguards Standard do-no-harm criteria

Project Verifier's Confirmation:

The *UCR Project Verifier* has verified the UCR project activity and therefore confirms the following:

The UCR Project Verifier *Enviance Services Private Limited*, certifies the following with respect to the UCR Project Activity [*136.5 MW Wind Power Projects in Brazil by Babilônia*].

☒ The Project Owner has correctly described the Project Activity in the Project Concept Note version 3 (dated 07/04/2025) including the applicability of the approved methodology [*ACM0002., Consolidated baseline methodology for grid-connected electricity generation from renewable sources - Version 21.0*] and meets the methodology applicability conditions and has achieved the estimated GHG emission reductions, complies with the monitoring methodology and has calculated emission reductions estimates correctly and conservatively.

☒ The Project Activity is likely to generate GHG emission reductions amounting to the estimated [581,227] tCO₂e, as indicated in the PCN version 3, which are additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable UCR rules, including ISO 14064-2 and ISO 14064-3.

	☒ The Project Activity is not likely to cause any net-harm to the environment and/or society ☒ The Project Activity complies with all the applicable UCR rules and therefore recommends UCR Program to register the Project activity with above mentioned labels.
Project Verification Report, reference number and date of approval	Verification Report UCR Reference number: 387 Date of approval: 17/04/2025
Name of the authorised personnel of UCR Project Verifier and his/her signature with date	Vidhya Murali Krishna  Quality Manager Date: 17/04/2025

PROJECT VERIFICATION REPORT

Executive summary

The project **136.5 MW Wind Power Projects in Brazil by Babilônia** consists of five (5) project activities installed in Brazil, located in the state of Bahia, at the Village Ourolândia. The promoter of the project is Babilônia Holding S.A., a company which has the full ownership of the project activity.

The purpose of the project activity is to generate electricity by harnessing the wind energy by the installation of Wind Turbine Generators (WTGs). The proposed project activity consists of five (5) project activities installed at the same location, clustered in a wind farm complex of total capacity 136.5 MW.

Commissioning dates and geo Co-ordinates of all the locations are mentioned in the table below:

Project Activity	Power Plant Name	Village/State	Energy Source	Number of turbines	Capacity of each WTG	Installed capacity in MW	Annual generation in MWh/year	Commissioning date
1	BABILÔNIA I	Ourolândia, BA	Wind	13	2.1	27.3	228,295	26/11/2018
2	BABILÔNIA II	Ourolândia, BA	Wind	13	2.1	27.3	257,927	26/11/2018
3	BABILÔNIA III	Ourolândia, BA	Wind	13	2.1	27.3	239,460	26/11/2018
4	BABILÔNIA IV	Ourolândia, BA	Wind	13	2.1	27.3	267,644	26/11/2018
5	BABILÔNIA V	Ourolândia, BA	Wind	13	2.1	27.3	364,683	14/11/2018

Project Activity	Country	State	Village	Latitude	Longitude
BABILÔNIA I	Brazil	Bahia	Ourolândia	10°54'46.9" S	41°13'17.1" W
BABILÔNIA II	Brazil	Bahia	Ourolândia	10°56'22.9" S	41°13'44.0" W
BABILÔNIA III	Brazil	Bahia	Ourolândia	10°57'29.5" S	41°14'0.3" W
BABILÔNIA IV	Brazil	Bahia	Ourolândia	10°58'34.0" S	41°13'11.8" W
BABILÔNIA V	Brazil	Bahia	Ourolândia	11°0'22.9" S	41°13'37.7" W

Proposed wind power project has evolved as a result of the policies of Government of Brazil, which encourages energy development from renewable sources. These policies have given fresh impetus to wind power generation. Also, by virtue of being a wind power plant, the proposed plant can be instantly started, stopped and quickly adjusted for power generation corresponding to variations in power/energy releases.

The generated power from the project activities is being supplied to the Brazilian electricity grid. The project owners have signed a long-term power purchase agreement with CCEE (Câmara de

Comercialização de Energia Elétrica). All five plants are commissioned and are currently operational and have been inter-connected to Morro do Chapéu II substation. Being a clean renewable energy source, wind power plants cause no negative impact on the environment. The project activity is thus promoting sustainable development, as defined by the United Nations, since economic advancement and progress have been fostered “(...) without compromising the ability of future generations to meet their own needs” (United Nations General Assembly, 1987, p. 43).

The project activity displaces an equivalent amount of electricity which would have otherwise been generated by fossil fuel dominant electricity grid. The estimated lifetime of the project activity is considered as 20 years for wind technology. In the Pre- project scenario the entire electricity, consumed by the customers or delivered to the grid by, would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources.

The main component of this project activity is wind turbine which consists of components like main tower, blades, nacelle, hub, main shaft, gear box, bearing and housing, brake and generator. The generation of power from wind turbines is a clean technology as there is no fossil fuel-fired or no GHG gases are emitted during the process. Thus, project activity leads to a reduction the GHG emissions as it displaces power from fossil fuel-based electricity generation in the regional grid. Since the project activity generates electricity through wind energy, it will not cause any negative impact on the environment and thereby contributes to climate change mitigation efforts. The project activity also contributes to SDG goals 7,8 and 13.

The crediting period of the project activity for this monitoring period is 05 years, 02 months in which total estimated electricity generation is 15,00,186 MWh and the total GHG emission reduction estimated is 581,227 tCO₂e.

The project activity replaces anthropogenic emissions of greenhouse gases (GHGs) at approximately 530,271 tCO₂e over the entire crediting period, displacing a calculated average of 1,358,010 MWh from the generation-mix of power plants connected to the Brazilian grid. Project activity will mitigate the total GHG emission reductions of 530,271 tCO₂ e over the entire crediting period, thereby contributing to climate change mitigation efforts.

Scope of Verification

The scope of the services for the project is to perform Project Verification of concerned Project Activity. The scope of verification is to assess the claims and assumptions made in the Project Concept Note (PCN) and Monitoring Report (MR) against the UCR criteria, including but not limited to, UCR program verification guidance document, UCR Standard, UCR Program Manual, and related rules and guidelines established under Program process.

Verification Process and Methodology

The verification process was undertaken by a competent verification team and involved the following,

- Desk review of documents and evidence submitted in context of the reference rules and guidelines issued by UCR,
- Undertaking/conducting site visit/remote audit, interview or interactions with the representative of the project owners/representatives,
- Reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate and preparing a draft verification opinion based on the auditing findings and conclusions

- Finalization of the verification opinion (this report)

Desk/Document review

A detailed desk review of the PCN, MR, Methodology and all other associated documentation and references took place in advance of the site visit, and additional documents that were not available for the desk review were requested for review during the site visit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face to face interviews with key stakeholders (including the project developers and where necessary, government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Follow up interviews/site visit

The verifier conducted remote audit and had requested for site photographs, short videos. A remote interview was conducted with the project owners and stakeholders.

Conclusion

Based on the work performed, the verifier concludes that in the project activity “136.5 MW Wind Power Projects in Brazil by Babilônia”, the information and data presented in the MR version 2 dated 07/04/2025 is in line with the Project Concept Note Version 3 dated 07/04/2025 and meets all relevant requirements of the UCR for UCR project activities. The UCR project activity correctly applies the methodology “ACM0002: Grid-connected electricity generation from renewable sources version 21.0” leading to result in real, measurable and long-term emission reductions achieved for the current monitoring period.

For the current monitoring period, verified emission reductions achieved by the project activity were as below;

Start date of monitoring period	14/11/2018
End date of monitoring period	31/12/2023
Emission reductions achieved	530,271 tCO ₂ eq

Project Verification team, technical reviewer and approver

Project Verification team

No.	Role	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)	Involvement in		
					Document review	Off-Site inspection	Interviews
1.	Team Leader/Technic	Singh	Ritu	Enviance Services Private Limited	Yes	Yes	Yes

	al Expert						
2.	V-V Trainee / Technic al Expert in Trainee	Mahajan	Swati	Enviance Services Private Limited	Yes	Yes	Yes

Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation (e.g. name of central or other office of UCR Project Verifier or outsourced entity)
1.	Technical reviewer	Internal	Kumar	Pankaj	Enviance Services Private Limited

Means of Project Verification

Desk/document review

A detailed desk review of the PCN, MR, methodology and all other associated documentation and references took place in advance of the remote audit, and additional documents that were not available for the desk review were requested for review during the remote audit. Additional information can be required to complete the verification, which may be obtained from other public and reliable sources or through telephone and face-to face interviews with key stakeholders (including the project developers and where necessary, Government and NGO representatives in the host country).

A list of all documents reviewed or referred to in the course of this verification is included in Appendix 3 below.

Off-site inspection

Date of off-site inspection: 26/02/2025			
No.	Activity performed Off-Site	Site location	Date
1.	a) An assessment of the implementation and operation of the project activity as per the PCN and UCR requirements b) Verification of the project design, as documented is sound and reasonable, and meets the identified criteria of UCR Standard Requirements and associated guidance c) Assessment to conformance with the certification criteria as laid out in the UCR	Village Ouroândia, State Bahia, Brazil	26/02/2025

	Standards; d) Evaluation of the conformance with the certification scope, including the GHG project and baseline scenarios, additionality; GHG sources, sinks, and reservoirs; and the physical infrastructure, activities, technologies and processes of the GHG project to the requirements of the UCR; e) Evaluation of the calculation of GHG emissions, including the correctness and transparency of formulae and factors used; assumptions related to estimating GHG emission reductions; and uncertainties; and determination whether the project could reasonably be expected to achieve the estimated GHG reduction/removals. f) Review of information flows for generating, aggregating and reporting of the parameters to be monitored g) To confirm that the operational and data collection procedures can be implemented in accordance with the Monitoring Plan h) Cross-check of information provided in the submitted documents and data from other sources available at site i) Review of calculations and assumptions made in determining the GHG data and estimated ERs, and an identification of QA/QC procedures in place to prevent, or identify and correct, any errors or omissions in the reported monitoring parameters j) Interviews of local Stakeholders		
--	--	--	--

Interviews

No.	Interview			Date	subject
	Last name	First name	Affiliation		
1.	Americo	Higor	Babilônia Holding S.A.	26/02/2025	Project Implementation, Monitoring plan, Project Boundary, Eligibility criteria, Host country requirements, Emission redSuction calculations Project implementation, monitoring, Local stakeholder consultation
2.	Santos	Janderson			
3.	Andrade	Larissa	Kosher Climate India Private Limited		
4.	-	Sreelakshmi			
5.	Thakur	Prachi			
6.	Montalvao	Carmira Nunes	Local stakeholders		
7.	Pereira Da Silva	Adriana			
8.	Correa	Daniel			
9.	Costa	Gracilene			
10.	Manzano	Clara			

Sampling approach

Not applicable.

Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	No. of CL	No. of CAR	No. of FAR
Green House Gas (GHG)			
Identification and Eligibility of project type	-	-	-
General description of project activity	-	-	-
Application and selection of methodologies and standardized baselines	-	-	-
- Application of methodologies and standardized baselines	01	-	-
- Deviation from methodology and/or methodological tool	-	-	-
- Clarification on applicability of methodology, tool and/or standardized baseline	01	-	-
- Project boundary, sources and GHGs	-	-	-
- Baseline scenario	-	-	-
- Estimation of emission reductions or net anthropogenic removals	01	-	-
- Monitoring Report	01	01	-
Start date, crediting period and duration	-	-	-
Environmental impacts	-	-	-

Project Owner- Identification and communication	-	-	-
Others	01	-	-
Total	05	01	-

Project Verification findings

Identification and eligibility of project type

Means of Project Verification	The project has an installation of a 136.5 MW wind power capacity and hence it qualifies as a large-scale project. This is confirmed based on the commissioning certificates and technical specifications. Since the project is a large-scale project, it has applied approved CDM large scale methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0. The Project owner has used valid MR form available at the UCR website for the preparation of MR for the current project activity. The project has prepared MR in line with UCR guidance and requirements.
Findings	No findings raised.
Conclusion	The UCR-approved format is used for description and the project meets the requirement of the UCR verification standard and UCR project standard. UCR project communication agreement was submitted to the verifier and the same has been verified. Methodology referenced and applied appropriately describing the project type. The eligibility of the project aggregator is verified using the UCR communication agreement, project correctly applies the verification standard, UCR project standard, and UCR regulations. The project activity is overall meeting the requirements of the UCR Verification standard and UCR project standard.

General description of project activity

Means of	The project activity involves the operation of a 136.5 MW of large-scale wind power project and its commissioning date and power evacuation at the substation were verified through the commissioning certificate of the project. The power purchase agreement confirms the companies/entities involved in the agreement for purchase of electricity from the 136.5 MW (2.1 MW x 65 wind turbines in Village Ourolândia, Bahia state, Brazil) project. The project consists of 5 project activities each consisting of 13 wind turbines each of 2.1 MW capacity in same village. Assessment team conducted documentation review of the PCN against the UCR program verification standard version 2.0 and UCR CoU Standard (project eligibility criteria) version 7.0 and the UCR-PCN-FORM Version 1.0. By checking the supporting documents, it is confirmed that the project is a greenfield wind power project, the project is located in Village Ourolândia, Bahia state, Brazil. The approximate geo-coordinates of the project locations are mentioned below.																																				
	<table><tr><th>Project Activity</th><th>Country</th><th>State</th><th>Village</th><th>Latitude</th><th>Longitude</th></tr><tr><td>BABILÔNIA I</td><td>Brazil</td><td>Bahia</td><td>Ourolândia</td><td>10°54'46.9" S</td><td>41°13'17.1" W</td></tr><tr><td>BABILÔNIA II</td><td>Brazil</td><td>Bahia</td><td>Ourolândia</td><td>10°56'22.9" S</td><td>41°13'44.0" W</td></tr><tr><td>BABILÔNIA III</td><td>Brazil</td><td>Bahia</td><td>Ourolândia</td><td>10°57'29.5" S</td><td>41°14'0.3" W</td></tr><tr><td>BABILÔNIA IV</td><td>Brazil</td><td>Bahia</td><td>Ourolândia</td><td>10°58'34.0" S</td><td>41°13'11.8" W</td></tr><tr><td>BABILÔNIA V</td><td>Brazil</td><td>Bahia</td><td>Ourolândia</td><td>11°0'22.9" S</td><td>41°13'37.7" W</td></tr></table>	Project Activity	Country	State	Village	Latitude	Longitude	BABILÔNIA I	Brazil	Bahia	Ourolândia	10°54'46.9" S	41°13'17.1" W	BABILÔNIA II	Brazil	Bahia	Ourolândia	10°56'22.9" S	41°13'44.0" W	BABILÔNIA III	Brazil	Bahia	Ourolândia	10°57'29.5" S	41°14'0.3" W	BABILÔNIA IV	Brazil	Bahia	Ourolândia	10°58'34.0" S	41°13'11.8" W	BABILÔNIA V	Brazil	Bahia	Ourolândia	11°0'22.9" S	41°13'37.7" W
	Project Activity	Country	State	Village	Latitude	Longitude																															
	BABILÔNIA I	Brazil	Bahia	Ourolândia	10°54'46.9" S	41°13'17.1" W																															
	BABILÔNIA II	Brazil	Bahia	Ourolândia	10°56'22.9" S	41°13'44.0" W																															
	BABILÔNIA III	Brazil	Bahia	Ourolândia	10°57'29.5" S	41°14'0.3" W																															
	BABILÔNIA IV	Brazil	Bahia	Ourolândia	10°58'34.0" S	41°13'11.8" W																															
BABILÔNIA V	Brazil	Bahia	Ourolândia	11°0'22.9" S	41°13'37.7" W																																
Assessment team performed an offsite inspection of project and confirmed that the location described in the PCN are accurate.																																					
The Project is a wind power project, to utilize wind energy to generate zero carbon emission electricity which is mainly dominated by fossil fuel power output. The project includes integrated power transmission mechanism, high performance rotor blades, dual speed asynchronous generator, microprocessor based fully automatic control system with user friendly operation and central monitoring system. Quality, Safety and Health plan for construction, installation, commissioning and Operation & Maintenance. Microprocessor controlled high efficiency soft start. Active Yaw gear drives incorporating hydraulic yaw brakes.																																					
Findings	CL 05 was raised and closed successfully. More information presented appendix below.																																				
Conclusion	The description of the project activity is verified to be true based on the review of PCN, MR, Commissioning Certificate and power purchase agreement.																																				

Application and selection of methodologies and standardized baselines

(.a.i) Application of methodology and standardized baselines

Means of Project Verification	The project has taken the reference of CDM methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0. CDM website is referred to check the latest version of the methodology. For the applicability mentioned in the PCN and MR, technical Specification, and commissioning certificate.
Findings	No findings raised.
Conclusion	The methodology applied is appropriately meeting the requirements of UCR and its standardized baseline. The methodology version is correct and valid. The referenced methodology is applicable to project activity.

(.a.ii) Clarification on applicability of methodology, tool and/or standardized baseline

Means of Project Verification	The documents reviewed are CDM methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0, UCR Program standard, and UCR Verification Standard.
Findings	CL 01 was raised and closed successfully. More information presented appendix below.
Conclusion	The verification team confirms that all the applicability criteria set by the applied CDM methodology and its eligible tools are met. The relevant information against those criteria is also included in the PCN ver. 3 and MR Ver.2. The selected CDM methodology for the project activity is applicable.

(.a.iii) Project boundary, sources and GHGs

Means of Project Verification	Project owner has considered project boundary as per applicable methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0, "The spatial extent of the project boundary includes the project power plant/unit and all power plants/units connected physically to the electricity system that the CDM project power plant is connected to." Review of PCN and MR confirms that project sites and Brazilian electricity grid system is considered as a project boundary which is appropriate.
Findings	No findings raised
Conclusion	The project boundary is correctly defined in the PCN and MR. GHG sources are correctly identified and reported. The project meets the requirements of UCR project standard, Verification standard and methodology requirements for a boundary, GHG sources.

(.a.iv) Baseline scenario

Means of Project Verification	As per the applied methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0 the baseline scenario is as following: The baseline scenario is electricity delivered to the grid by the project activity that would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources.
--------------------------------------	--

	Remote audit conducted and document review showed that in absence of the project activity, the generated electricity would have been supplied by the Brazilian grid which is dominated by fossil fuel fired plants.
Findings	No findings raised.
Conclusion	The approved baseline methodology has been correctly applied to identify a realistic and credible baseline scenario, and the identified baseline scenario most reasonably represents what would occur in the absence of the proposed UCR project activity. All the assumption and data used by the project participants are listed in the PCN and/or supporting documents. All documentation relevant for establishing the baseline scenario are correctly quoted and interpreted in the PCN. Assumptions and data used in the identification of the baseline scenario are justified appropriately, supported by evidence and can be deemed reasonable.

(.a.v) Estimation of emission reductions or net anthropogenic removal

Means of Project Verification	The project verification team checked whether the equations and parameters used to calculate GHG emission reductions or net anthropogenic GHG removals for PCN and MR are in accordance with applied methodology. Project verification team checked section B.5 and C.5.1 of the PCN & MR respectively to confirm whether all formulae to calculate baseline emissions, project emission and leakage have been applied in line with the underlying methodology. The emission reduction calculation has been carried out as per the CDM methodology ACM0002, Version 21.0. $BE_y = EGPJ_y \times EF_{Grid,y}$ Where, BE_y = Baseline emissions in year y (t CO₂) $EGPJ_y$ = Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the CDM project activity in year y (MWh) $EF_{Grid,y}$ = Grid emission factor in year y (t CO₂/MWh) A "grid emission factor" refers to a CO₂ emission factor (tCO₂/MWh) which will be associated with each unit of electricity provided by an electricity system. The grid emission factor suggested by the Brazilian grid is referred here, https://www.gov.br/mcti/pt-br/acompanhe-o-mcti/cgcl/paginas/metodo-da-analise-de-despacho. The combined margin of the Brazil grid used for the project activity is as follows: <table border="1"> <thead> <tr> <th>Parameter</th><th>Value</th><th>Nomenclature</th><th>Source</th></tr> </thead> <tbody> <tr> <td>$EF_{grid,CM,y}$</td><td>As given below</td><td>Combined margin CO₂ emission factor for the project electricity system in year y.</td><td>Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO₂ emission factors for electricity generation</td></tr> </tbody> </table>			Parameter	Value	Nomenclature	Source	$EF_{grid,CM,y}$	As given below	Combined margin CO ₂ emission factor for the project electricity system in year y.	Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation
Parameter	Value	Nomenclature	Source								
$EF_{grid,CM,y}$	As given below	Combined margin CO ₂ emission factor for the project electricity system in year y.	Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation								

			in the National Interconnected System of Brazil.
$EF_{grid,OM,y}$	As given below	Operating margin CO_2 emission factor for the project electricity system in year y.	Calculated from the monthly average emission, sourced from Ministry of Science and Technology “ CO_2 emission factors for electricity generation in the National Interconnected System of Brazil.
$EF_{grid,BM,y}$	As given below	Build margin CO_2 emission factor for the project electricity system in year y.	The built margin value has been sourced from Ministry of Science and Technology “ CO_2 emission factors for electricity generation in the National Interconnected System of Brazil.

Year	Operating Margin Emission Factor	Build Margin Emission Factor	Combined Margin Emission Factor
2018	0.5390	0.137	0.4385
2019	0.5181	0.1020	0.4140
2020	0.4539	0.0979	0.3649
2021	0.5985	0.0540	0.4623
2022	0.3963	0.0270	0.3039
2023	0.3785	0.0467	0.2956

Project emissions: As per paragraph 35 of the applied methodology, For most renewable energy project activities,
 $PE_y = 0$.
Since wind power is a GHG emission free source of energy project emission considered as Zero for the project activity.

Leakage Emissions: As per the paragraph 61 of the applied methodology ACM0002 Version 21.0, there are no emissions related to leakage in this project.
 $LE_y = 0$.

Emission reductions: As per Paragraph 62, equation 17 of the applied methodology, emission reductions are calculated as follows
 $ER_y = BE_y - PE_y$
Where: ER_y = Emission reductions in year y (tCO_2)
 BE_y = Baseline Emissions in year y (tCO_2)
 PE_y = Project emissions in year y (tCO_2)
 LE_y = Leakage emissions in year y (tCO_2)

Therefore, $ER_y = BE_y$

The start date of the Project is from 14/11/2018 which is the earliest Commissioning date. For the ease of the calculation, duration of the crediting period is started from 14/11/2018 to 31/12/2023
The estimated emission reductions are:

		<table><tr><th>Crediting period</th><th>Net Generation free from I-REC (MWh/year)</th><th>Emission Factor (tCO₂/MWh)</th><th>Emission Reduction (tCO₂/year)</th></tr><tr><td>14-11-2018 to 31-12-2018</td><td>81,149</td><td>0.44</td><td>35,543</td></tr><tr><td>01-01-2019 to 31-12-2019</td><td>635,012</td><td>0.41</td><td>262,939</td></tr><tr><td>01-01-2020 to 31-12-2020</td><td>118,595</td><td>0.36</td><td>43,275</td></tr><tr><td>01-01-2021 to 31-12-2021</td><td>235,012</td><td>0.46</td><td>108,668</td></tr><tr><td>01-01-2022 to 31-12-2022</td><td>425,574</td><td>0.30</td><td>129,370</td></tr><tr><td>01-01-2023 to 31-12-2023</td><td>4,845</td><td>0.30</td><td>1,432</td></tr><tr><td>Total</td><td>1,500,186</td><td></td><td>581,227</td></tr></table>	Crediting period	Net Generation free from I-REC (MWh/year)	Emission Factor (tCO ₂ /MWh)	Emission Reduction (tCO ₂ /year)	14-11-2018 to 31-12-2018	81,149	0.44	35,543	01-01-2019 to 31-12-2019	635,012	0.41	262,939	01-01-2020 to 31-12-2020	118,595	0.36	43,275	01-01-2021 to 31-12-2021	235,012	0.46	108,668	01-01-2022 to 31-12-2022	425,574	0.30	129,370	01-01-2023 to 31-12-2023	4,845	0.30	1,432	Total	1,500,186		581,227	
	Crediting period	Net Generation free from I-REC (MWh/year)	Emission Factor (tCO ₂ /MWh)	Emission Reduction (tCO ₂ /year)																															
	14-11-2018 to 31-12-2018	81,149	0.44	35,543																															
	01-01-2019 to 31-12-2019	635,012	0.41	262,939																															
	01-01-2020 to 31-12-2020	118,595	0.36	43,275																															
	01-01-2021 to 31-12-2021	235,012	0.46	108,668																															
	01-01-2022 to 31-12-2022	425,574	0.30	129,370																															
	01-01-2023 to 31-12-2023	4,845	0.30	1,432																															
	Total	1,500,186		581,227																															
	The actual emission reduction achieved during the first CoU's period (14/11/2018 to 31/12/2023) as per the Project Activity:																																		
	<table><tr><th>Crediting period</th><th>Net Generation free from I-REC (MWh/year)</th><th>Emission Factor (tCO₂/MWh)</th><th>Emission Reduction (tCO₂/year)</th></tr><tr><td>14-11-2018 to 31-12-2018</td><td>74,230.90</td><td>0.44</td><td>32,513.13</td></tr><tr><td>01-01-2019 to 31-12-2019</td><td>639,540.21</td><td>0.41</td><td>264,813.61</td></tr><tr><td>01-01-2020 to 31-12-2020</td><td>60,847.25</td><td>0.36</td><td>22,203.16</td></tr><tr><td>01-01-2021 to 31-12-2021</td><td>210,827.85</td><td>0.46</td><td>97,485.78</td></tr><tr><td>01-01-2022 to 31-12-2022</td><td>372,563.93</td><td>0.30</td><td>113,256</td></tr><tr><td>01-01-2023 to 31-12-2023</td><td>0</td><td>0.30</td><td>0</td></tr><tr><td>Total</td><td>1,358,010</td><td></td><td>530,271</td></tr></table>	Crediting period	Net Generation free from I-REC (MWh/year)	Emission Factor (tCO ₂ /MWh)	Emission Reduction (tCO ₂ /year)	14-11-2018 to 31-12-2018	74,230.90	0.44	32,513.13	01-01-2019 to 31-12-2019	639,540.21	0.41	264,813.61	01-01-2020 to 31-12-2020	60,847.25	0.36	22,203.16	01-01-2021 to 31-12-2021	210,827.85	0.46	97,485.78	01-01-2022 to 31-12-2022	372,563.93	0.30	113,256	01-01-2023 to 31-12-2023	0	0.30	0	Total	1,358,010		530,271		
Crediting period	Net Generation free from I-REC (MWh/year)	Emission Factor (tCO ₂ /MWh)	Emission Reduction (tCO ₂ /year)																																
14-11-2018 to 31-12-2018	74,230.90	0.44	32,513.13																																
01-01-2019 to 31-12-2019	639,540.21	0.41	264,813.61																																
01-01-2020 to 31-12-2020	60,847.25	0.36	22,203.16																																
01-01-2021 to 31-12-2021	210,827.85	0.46	97,485.78																																
01-01-2022 to 31-12-2022	372,563.93	0.30	113,256																																
01-01-2023 to 31-12-2023	0	0.30	0																																
Total	1,358,010		530,271																																
Findings	CL 02 was raised and closed successfully. More information presented appendix below.																																		
Conclusion	In summary, the calculation of emission reductions was correctly demonstrated by the PP according to the methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0 It is confirmed by the assessment team that: (a) All assumptions made for estimating GHG are listed in the PCN; (b) All documentation used by the project participants as the basis for assumptions and source of data is correctly quoted and interpreted in the PCN (c) All values used in the PCN including GWPs are considered reasonable in the context of the proposed UCR project activity; (d) The methodologies and, where applicable, the standardized baselines and the other																																		

	methodological regulatory documents have been applied correctly to calculate baseline, project and leakage GHG emissions, as well as GHG emission reductions; (e) All estimates of the baseline GHG emissions can be replicated using the data and parameter values provided in the PCN;
--	--

(.a.vi) Monitoring Report

Means of Project Verification	Parameters determined- Ex-ante																											
	The following parameters are determined ex-ante and verified by the verification team:																											
	The baseline emission factor ($EF_{grid, y}$) of the project is reported to be determined ex-ante and would remain fixed for the crediting period.																											
	A "grid emission factor" refers to a CO ₂ emission factor (tCO ₂ /MWh) which will be associated with each unit of electricity provided by an electricity system.																											
	The grid emission factor suggested by the Brazilian grid is referred here, https://www.gov.br/mcti/pt-br/acompanhe-o-mcti/cgcl/paginas/metodo-da-analise-de-despacho .																											
	The combined margin of the Brazil grid used for the project activity is as follows:																											
	<table><tr><th>Parameter</th><th>Value</th><th>Nomenclature</th><th>Source</th></tr><tr><td>$EF_{grid,CM,y}$</td><td>As given below</td><td>Combined margin CO₂ emission factor for the project electricity system in year y.</td><td>Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO₂ emission factors for electricity generation in the National Interconnected System of Brazil.</td></tr><tr><td>$EF_{grid,OM,y}$</td><td>As given below</td><td>Operating margin CO₂ emission factor for the project electricity system in year y.</td><td>Calculated from the monthly average emission, sourced from Ministry of Science and Technology "CO₂ emission factors for electricity generation in the National Interconnected System of Brazil.</td></tr><tr><td>$EF_{grid,BM,y}$</td><td>As given below</td><td>Build margin CO₂ emission factor for the project electricity system in year y.</td><td>The built margin value has been sourced from Ministry of Science and Technology "CO₂ emission factors for electricity generation in the National Interconnected System of Brazil.</td></tr></table>	Parameter	Value	Nomenclature	Source	$EF_{grid,CM,y}$	As given below	Combined margin CO ₂ emission factor for the project electricity system in year y.	Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.	$EF_{grid,OM,y}$	As given below	Operating margin CO ₂ emission factor for the project electricity system in year y.	Calculated from the monthly average emission, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.	$EF_{grid,BM,y}$	As given below	Build margin CO ₂ emission factor for the project electricity system in year y.	The built margin value has been sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.											
	Parameter	Value	Nomenclature	Source																								
	$EF_{grid,CM,y}$	As given below	Combined margin CO ₂ emission factor for the project electricity system in year y.	Calculated as the weighted average of the operating margin (0.75) & build margin (0.25) values, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.																								
	$EF_{grid,OM,y}$	As given below	Operating margin CO ₂ emission factor for the project electricity system in year y.	Calculated from the monthly average emission, sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.																								
$EF_{grid,BM,y}$	As given below	Build margin CO ₂ emission factor for the project electricity system in year y.	The built margin value has been sourced from Ministry of Science and Technology "CO ₂ emission factors for electricity generation in the National Interconnected System of Brazil.																									
<table><tr><th>Year</th><th>Operating Margin Emission Factor</th><th>Build Margin Emission Factor</th><th>Combined Margin Emission Factor</th></tr><tr><td>2018</td><td>0.5390</td><td>0.137</td><td>0.4385</td></tr><tr><td>2019</td><td>0.5181</td><td>0.1020</td><td>0.4140</td></tr><tr><td>2020</td><td>0.4539</td><td>0.0979</td><td>0.3649</td></tr><tr><td>2021</td><td>0.5985</td><td>0.0540</td><td>0.4623</td></tr><tr><td>2022</td><td>0.3963</td><td>0.0270</td><td>0.3039</td></tr><tr><td>2023</td><td>0.3785</td><td>0.0467</td><td>0.2956</td></tr></table>	Year	Operating Margin Emission Factor	Build Margin Emission Factor	Combined Margin Emission Factor	2018	0.5390	0.137	0.4385	2019	0.5181	0.1020	0.4140	2020	0.4539	0.0979	0.3649	2021	0.5985	0.0540	0.4623	2022	0.3963	0.0270	0.3039	2023	0.3785	0.0467	0.2956
Year	Operating Margin Emission Factor	Build Margin Emission Factor	Combined Margin Emission Factor																									
2018	0.5390	0.137	0.4385																									
2019	0.5181	0.1020	0.4140																									
2020	0.4539	0.0979	0.3649																									
2021	0.5985	0.0540	0.4623																									
2022	0.3963	0.0270	0.3039																									
2023	0.3785	0.0467	0.2956																									
Hence, the same emission factor has been considered to calculate the emission reduction under conservative approach. The parameters applied in the calculation were validated by the verification team. The verification team confirms that all relevant parameters have been sufficiently considered and the values of the parameters are real, measurable and conservative.																												
Parameters monitored ex-post																												

According to the approved methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0, the following parameters will be monitored:

Parameter	Description
EG _{PJ,y}	Quantity of net electricity generation supplied by the projectplant/unit to the grid in year y

The values of the parameters monitored were checked against submitted Joint Meter Readings and invoices and were found correct.

Meters details:

		Main Mater			Back-Up Meter		
	Type of meter	Bidirectional Meter			Bidirectional Meter		
	Location of meter	Power plant site			Power plant site		
	Accuracy of meter	0.2s			0.2s		
	Serial number of meters	Proj. Act.	Series nº		Proj. Act.	Series nº	
		1	MW-1707A005-02		1	MW-1706A781-02	
		2	MW-1706B374-02		2	MW-1707A024-02	
		3	MW-1706B451-02		3	MW-1706A865-02	
		4	MW-1706A757-02		4	MW-1706B476-02	
		5	MW-1706B470-02		5	MW-1706A693-02	
	Calibration frequency	Once every 5 years			Once every 5 years		
	Date of Calibration/ validity	2017:			2017:		
		Main Meter nº	Calibration date	Calibration validity	Back-up Meter nº	Calibration date	Calibration validity
		MW-1707A005-02	30/08/2017	30/08/2022			
		MW-1706B374-02	31/08/2017	31/10/2022	MW-1706A781-02	15/09/2017	15/09/2022
		MW-1706B451-02	31/08/2017	31/10/2022	MW-1707A024-02	31/08/2017	31/10/2022
		MW-1706A757-02	30/08/2017	30/08/2022	MW-1706A865-02	15/09/2017	15/09/2022
MW-1706B470-02		31/08/2017	31/10/2022	MW-1706B476-02	31/08/2017	31/10/2022	
				MW-1706A693-02	30/08/2017	30/08/2022	
2024:			2024:				
Main Meter nº		Calibration date	Calibration validity	Main Meter nº	Calibration date	Calibration validity	
MW-1707A005-02		09/01/2024	09/01/2029	MW-1706A781-02	09/01/2024	09/01/2029	
MW-1706B374-02		09/01/2024	09/01/2029	MW-1707A024-02	09/01/2024	09/01/2029	
MW-1706B451-02		09/01/2024	09/01/2029	MW-1706A865-02	09/01/2024	09/01/2029	
MW-1706A757-02		10/01/2024	10/01/2029	MW-1706B476-02	10/01/2024	10/01/2029	
MW-1706B470-02		10/01/2024	10/01/2029	MW-1706A693-02	10/01/2024	10/01/2029	

Reference No. of Calibration Certificate	2017:		2017:	
	Proj. Act.	Certificate n°	Proj. Act.	Certificate n°
	1	9809/Z-17	1	9667/Z-17
	2	9840/Z-17	2	9869/Z-17
	3	9835/Z-17	3	9974/Z-17
	4	9814/Z-17	4	9830/Z-17
	5	9826/Z-17	5	9813/Z-17
	2024:		2024:	
	Proj. Act	Certificate n°	Proj. Act	Certificate n°
	1	CC-0853-24	1	CC-0854-24
	2	CC-0855-24	2	CC-0856-24
	3	CC-0857-24	3	CC-0858-24
	4	CC-0859-24	4	CC-0860-24
	5	CC-0861-24	5	CC-0862-24
Calibration Status	Calibrated		Calibrated	

The backup meters are installed alongside the main meters on the same panel, providing the same information for current and voltage, meeting the same technical standard Qualified organizations, adhering to national standards and regulations, conduct meter calibration to ensure accurate measurements.

The calibration of plant-end meters will be carried out once in 5 years or whenever abnormal difference/inconsistency is observed between main meters and back-up meters.

There is calibration delay for the monitoring period from September 2022 to December 2023. The error factor has been applied in net export values for delay period as meters were not calibrated as per the calibration frequency. As per VVS requirement: error factor of "±0.2%" should be applicable for both export & import i.e. the measured values. Hence being conservative and to account for the error for both export & import, a cumulative error of “-0.2% on export and +0.2% for import values” has been applied for delay period.

Management system and quality assurance

The monitoring plan presented in the PCN complies with the requirements of the applicable methodology. The verification team has verified all parameters in the monitoring plan against the requirements of the methodology and no deviations have been found.

The management system and quality assurance procedures have been reviewed by the verification team through document review and interviews with the project participant. The project participant would train all the monitoring staffs are trained against with related requirement; the training guidelines and monitoring manual are saved and verified.

The monitoring plan outlines in the PCN includes:

- Monitoring Organization

	- Monitoring apparatus and installation - Calibration - Data collection - Data Management system The submitted calibration certificates were checked and it was confirmed that the calibrations are conducted periodically as specified in the PCN i.e. at least once in 5 years. Error factor has been taken into account for the delayed calibration during the current monitoring period.
Findings	CL 04 and CAR 01 were raised and closed successfully. More information presented in the appendix below.
Conclusion	The verification team is convinced of compliance of the monitoring plan with the requirements of the monitoring methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0. During the remote audit assessment, the verification team interviewed the PP that the monitoring arrangements described in the monitoring plan are feasible within the project design. The monitoring parameter reported in MR adequately represents the parameters relevant to emission reduction calculation. The calibration report ensures the accuracy of the data reported. The number of CoUs generation is calculated based on this accurately reported data. The calculation was done using an excel sheet where all the parameters were reported. The grid emission factor for electricity is considered as per the Brazilian national interconnected system. In the monitoring report, emission reduction calculations are correctly calculated and reported. The monitoring report meets the requirements of UCR project verification requirements.

Start date, crediting period and duration

Means of Project Verification	The start date and crediting period of project activity was checked based on the commissioning certificate, PCN, MR and other documents provided.
Findings	No findings raised.
Conclusion	The project has chosen crediting period start date as 14/11/2018. The crediting period is chosen as 14/11/2018 to 31/12/2023 and the crediting period for the current monitoring period is 14/11/2018 to 31/12/2023.

Positive Environmental impacts

Means of Project Verification	PP has not claimed any separate positive environmental impact. The project being renewable energy project will reduce fossil fuel use through replacement of the same.
Findings	No findings raised
Conclusion	The project is a renewable energy project and reduces the environmental burden by reducing the dependence on fossil fuel-based power plants.

Project Owner- Identification and communication

Means of Project Verification	PCN, communication agreement, MR, commissioning certificate, power purchase agreement.
Findings	No findings raised

Conclusion	The project owner was identified through a communication agreement signed between project owner and project aggregator. Commissioning certificates and Power Purchase Agreement were also verified and they clearly establish the project ownership. The identification and communication correctly meet the requirement of project verification and UCR project standard. Project owner: Babilônia Holding S.A.
-------------------	--

Positive Social Impact

Means of Project Verification	Project has provided temporary employment to local people during its installation and commissioning. Also post commissioning some of people have employed permanently and local people were engaged leading to social financial benefit to surrounding. Overall social impact of project implementation is positive on the surrounding area
Findings	CL 03 was raised and closed successfully. More information presented in the appendix below.
Conclusion	Project has overall positive social impact

Sustainable development aspects (if any)

Means of Project Verification	PP has claimed SDG Goals 7, 8 & 13. SDG 7 is affordable and clean energy and it is verified during remote audit as the project is wind power plant. SDG 8 is decent work & economic growth and is verified by the supporting documents. SDG 13 is climate action. These claims were checked on the basis of supporting documents, JMR & invoice, employment of the local people on the project site and emission reduction calculations respectively.
Findings	No findings raised.
Conclusion	The project has the capability to address SDG 7, 8 and 13.

Internal quality control

The verifier confirms that,

- Due professional care has been taken while reviewing the submitted document.
- There is no conflict of interest as the verifier has no other engagement with either the aggregator or project owner directly or indirectly.
- Verification team consists of experienced personnel.

Project Verification opinion

Assessment team conducted documentation review the PCN against the UCR program verification standard version 2.0 and UCR project eligibility criteria version 7.0 and the UCR-PCN-FORM Version 1.0.

It is confirmed that the project activity is a 136.5 MW of large-scale wind power project (2.1 MW x 65 wind turbines) in Village Ouroândia, Bahia State, Brazil. The geo co-ordinates of the project activity have been mentioned in sections above. Assessment team performed an offsite audit and confirmed that the location described in the PCN is accurate. The verification was performed on the basis of UCR requirements, and host country criteria, as well as criteria given to provide for consistent project operations, monitoring and reporting.

The verification consisted of the following three phases: i) desk review of the PCN, MR and additional background documents; ii) follow-up interviews with project stakeholders; iii) resolution of outstanding issues and the issuance of the final verification report and opinion.

The project correctly applies the approved baseline and monitoring methodology ACM0002: Grid-connected electricity generation from renewable sources version 21.0.

The monitoring plan provides for the monitoring of the project's emission reductions. The monitoring arrangements described in the monitoring plan are feasible within the project design, and the project participants are able to implement the monitoring plan. Given that the project is implemented and maintained as designed, the project has achieved the emission reductions of 530,271 tCO₂eq during the monitoring period i.e. from 14/11/2018 to 31/12/2023.

The review of the project design documentation and the subsequent follow-up interviews have provided assessment team with sufficient evidence to determine the fulfilment of stated criteria. In our opinion, the project meets all applicable UCR requirements. Assessment team thus requests the registration of the proposed UCR project activity.

Appendix 1. Abbreviations

Abbreviations	Full texts
ACM	Approved Methodology for large-Scale CDM project activities
UCR	Universal Carbon Registry
PCN	Project Concept Note
MR	Monitoring Report
t	Tonnes
NGO	Non-Governmental Organization
ISO	International Organization for Standardization
CAR	Corrective Action Request

CL	Clarification Request
GHG	Greenhouse Gas
MWh	Megawatt Hours
CO ₂	Carbon Dioxide
CH ₄	Methane
N ₂ O	Nitrous Oxide

Appendix 2. Competence of team members and technical reviewers

- ❖ **Mr. Pankaj Kumar** worked as team leader – Bihar for South Asia Climate Proofing and Growth Development (CPGD) – Climate Change Innovation Programme (CCIP) supported by DFID that seeks to mainstream climate change resilience into planning and budgeting at the national and sub-national level in India, Pakistan, Nepal, and Afghanistan. Pankaj Kumar has worked previously with IL&FS Infrastructure Development Corporation and BUIDCO (Bihar Urban Infrastructure Development Corporation), Govt. of Bihar as Environmental Specialist for WB & ADB funded projects. Prior to this, he worked with Carbon Check (UNFCCC accredited DoE), Johannesburg, RSA, Applus certification as Team Leader for validation, verification of around 100 GHG projects in Asia, Africa, USA, Asia Pacific & Americas. Pankaj is accredited Lead Auditor, Validator, Verifier and Technical Expert for Sectoral Scope/Technical Area – 1.1, 1.2, 3.1, 4.1, 13.1 by Enviance. He is also member of task force on climate change & human health, Health Department, GoB and on roster of UNICEF's WASH experts. He is an experienced, qualified and result oriented Environment Professional having more than 14 yrs. of relevant experience in Climate Change (Mitigation & Adaptation), Environmental Due Diligence, Disaster Risk Reduction, Validation and Verification of GHG project under CDM, Verified Carbon Standard, Gold Standard & Social Carbon Standard, Brazil. He provides technical support for environmental investigative, consultative and remedial projects involving air, water and soil, Waste management, EIA, Environmental Compliance, ISO 14001, OHSAS 18001, GHG accounting (ISO 14064) and Carbon foot printing. Pankaj Kumar is Masters in Environment Management from Forest Research Institute (University), I.C.F.R.E, Dehradun, which is Centre of Excellence in South East Asia for Forestry education & research and PGDEL from National Law School of India University, Bangalore (India).
- ❖ **Ms. Ritu Singh** has done Masters in Environmental Science from Central University of South Bihar, Gaya and bachelor of Science in Zoology from Magadh Mahila College, Patna University, India. She has done Masters' research focused on solid waste management during and post covid-19 pandemic and conducted a survey in Medical Colleges of Bihar to study the trends of waste management. She has more than 2 year working experience in True Quality Certifications Pvt. Ltd. (An outsource entity for

LGAI Technological Center, S.A. (Spain) "Applus+ Certification") and has been involved in supporting Audit teams for Validation and Verifications of Project Activities (Renewable and non-Renewable projects) under CDM/VCS/GS4GG/GCC programs. Currently, Ritu is engaged as an internal resource with Enviance Services Private Limited, where she is accredited as a Lead Auditor, Validator, Verifier, and Technical Expert for Sectoral Scope/Technical Area 1.2 by Enviance.

- ❖ **Ms. Swati Mahajan** is graduate in Environmental Engineering from Shivaji University, India and previously worked as an Environment Engineer at Eco Designs India Private Ltd., Pune. She is adept in designing of landfill sites for solid waste management. She also has hands on experience in cost benefit analysis and preparation of DPRs for SWM projects. She also has done a certified course in carbon capture and storage from Edinburg University. Currently working as GHG assessor for projects under various GHG mechanisms like GCC, ICR, UCR and VERRA.

Appendix 3. Document reviewed or referenced

No.	Author	Title	References to the document	Provider
1	NA	Communication agreement		Project Owner
2	NA	Project Concept Note		Aggregator
3	NA	Monitoring report		Aggregator
4	NA	Emission reduction sheet		Aggregator
5	NA	Declaration on avoidance of double counting		Aggregator
6	NA	Commissioning Certificates for the solar power plants		Aggregator
7	NA	Power purchase agreement		Aggregator
8	NA	Joint Meter Readings/invoices for the complete monitoring period		Aggregator
9	NA	Calibration certificates for energy meters		Aggregator
10	NA	Equipment purchase order		Aggregator
11	NA	Grid Emission factor recommended by Brazilian National Interconnected System	https://www.gov.br/mcti/pt-br/acompanhe-o-mcti/cgcl/paginas/metodo-da-analise-de-despacho	Brazilian ministry of science and technology
12	UCR	UCR Program manual version 6.1 UCR COU standard version 7 UCR Verification standard version 2 UCR terms and conditions		Universal Carbon Registry

13	CDM	CDM approved methodology- ACM0002: Grid Connected electricity generation from renewable sources version 21.0		UNFCCC
----	-----	---	--	--------

Appendix 4. Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
1. PP shall submit the photographs of project activity showcasing the clear pictures of the windmills. 2. PP shall submit the list of the names of the local stakeholders.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025
1. Photographs of the project activity are submitted for reference. 2. Employment records have been shared for review.			
Validation/Verification Team Assessment		Date:	03/04/2025
1. PP has submitted the photographs of the project activity showcasing the clear pictures of the windmills. Assessment team has verified the pictures and found to be consistent with the submitted documents. 2. PP has submitted the list of the names of the local stakeholders. Verifier has assessed the document. Hence, this part of CL is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	02
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
1. PP shall add meter details and calibration details in MR 2. As per submitted calibration certificate, meter calibration date is June 2017. As mentioned in MR meters are calibrated once in 5 years. PP should submit recent calibration report or add error factor in all the values which are monitored after the calibration due date. Clarification sought.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025

1. Meter and calibration details are included in the MR. 2. Recent calibration certificates have been submitted for reference.		
Validation/Verification Team Assessment	Date:	03/04/2025
1. PP has included meter and calibration details in MR. Verifier has verified the same in MR version 2.0. 2. As per the calibration details in MR and the submitted calibration certificate, first calibration is valid from 03/08/2017 to 03/08/2022 and the second calibration is valid from 09/01/2024 to 09/01/2029. There is a calibration delay from 03/09/2022 to 08/01/2024. PP shall apply an error factor to the values from august 2022 to December 2023. Accordingly update values in MR. Hence, this part of CL is open.		
Client/Responsible Party/Project Proponent Response	Date:	07/04/2025
The first calibration certificate is valid until 30/08/2022, and the second calibration is effective from 09/01/2024. Since there is no valid calibration certificate covering the period between these two dates, the error factor has been applied to the values corresponding to this gap		
Validation/Verification Team Assessment	Date:	08/04/2025
1. PP has included meter and calibration details in MR. Verifier has verified the same in MR version 2.0. 2. As per the VVR requirements PP has applied an error factor of “-02%” to export values and “+0.2%” to import values. Assessment team has verified the same in updated ER sheet and found to be consistent. PP has updated the valued in MR and the same has been verified in MR version 2.0. Hence, this part of CL is closed.		

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	03
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
In MR section B.2 and in PCN section A.2, PP shall add details of all the SDG goals which are claimed by the project activity. PP shall also provide the supporting documents for the same.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025
Details of all the SDG goals claimed by the project activity are included in section B.2 of the MR and section A.2 of the PCN. JMR/invoice and employment records are submitted as the supporting documents for the SDG goals claimed.			
Validation/Verification Team Assessment		Date:	03/04/2025
PP has added the SDG goals claimed by the project activity in section B.2 of the MR and section A.2 of the PCN. The same has been verified in MR version 2.0 and PCN version 3.0. PP has also submitted the supporting document for claimed SDG goals and are found to be consistent by the verifier. Hence, this part of CL is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	04
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
In PCN & MR, PP shall mention the details of power purchase agreement and power substation.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025
Details of power purchase agreement as well as the substation details are included in the PCN and MR.			
Validation/Verification Team Assessment		Date:	03/04/2025
PP has mentioned details of power purchase agreement and substations in both PCN and MR. Verifier has verified the same in PCN version 3.0 and MR version 2.0. Hence, this part of CL is closed.			

Classification	☐ CAR ☒ CL/CR ☐ FAR	Number:	05
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
PP shall submit the single line diagram of the project activity. The same should be added in PCN & MR.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025
The single line diagram of the project activity is submitted. The same is incorporated in the PCN & MR.			
Validation/Verification Team Assessment		Date:	03/04/2025
PP has submitted the single line diagram of the project activity and the same been assessed by the verifier. Hence, this part of CL is closed.			

Table 2. CARs from this Project Verification

Classification	☒ CAR ☐ CL/CR ☐ FAR	Number:	01
Raised by:	Ms. Ritu Singh	Document Reference	PCN & MR
Finding Description		Date:	03/03/2025
1. In MR, PP shall mention the actual values of energy generation and carbon emissions and not the estimated values. Correction Sought. 2. In PCN, PP shall mention only the estimated values of energy generation and carbon emissions and not the actual values. Correction Sought.			
Client/Responsible Party/Project Proponent Response		Date:	02/04/2025
1. The MR has been updated with actual values of energy generation and emission reductions. 2. The PCN has been updated with estimated values of energy generation and emission reductions			

Validation/Verification Team Assessment	Date:	03/04/2025
1. PP has updated the MR with actual values of energy generation and emission reductions and the same has been verified in MR version 2.0. 2. PP has updated the PCN with estimated values of energy generation and emission reductions and the same has been verified in PCN version 3.0. Hence, this part of CAR is closed.		

Table 3. FARs from this Project Verification

FAR ID	xx	Section no.		Date: DD/MM/YYYY
Description of FAR				
Project Owner's response				Date: DD/MM/YYYY
Documentation provided by Project Owner				
UCR Project Verifier assessment				Date: DD/MM/YYYY